BRUHAT BANGALORE MAHANAGAR PALIKE

Project Division, Yelahanka Zone

MODIFIED SCHEDULE - B

Drilling of Borewells, Installation of Pump and motors, Providing Pipeline and additional motor pumps and necessary accessories to existing borewells in ward no.06

SNo	Quantity	Item Name	Unit	Approved Rates of M/s SATHYA BOREWELL CLEANING	
				In figures	In words
1	47.00	Geophysical investigation of site for sinking borewell for supplying drinking water to the habitation either through the hand pump, MWS or P.W.S.S. by vertical electrical sounding by adopting venner or schlumbergers's method, including reconnaissance survey of geological formation, Geological investigation of existing ground water in vicinity, its quality, quantity & acceptability of the users indicating the location of site, recommended depth of casing pipe required to seal the top unconsolidated formation including an extra depth of 1.0 mtr in consolidated formation for proper seating of casing pipe, depth of drilling required to cover full depth of aquifer proposed to be tapped, probable yield and other information required including transportation of instrument and accessories to work site, engaging technical personal and labour required etc **Qty Upto 125%**	Each BW	4228.00	Rupees Four Thousand Two Hundred Twenty Eight Only
2	2350.00	Sinking of borewell of 165 mm dia clear using super fast hydraulic rig of capacity 250 PSIG & above 900 CMF & above in all strata including over budern upto 20 m. fixing of casing pipes, collars & cap with necessary cutting, threading & welding including transportation of rig and supporting vehicle, crew charges & cost of consumables etc., complete including yield testing at the final depth with minimum working of compressor for one hour(excluding cost of casing pipes, collars, cap etc.,) 0 to 50 m **Qty Upto 125%**	Rmtr	389.00	Rupees Three Hundred Eighty Nine Only
3	2350.00	Sinking of borewell of 165 mm dia clear using super fast hydraulic rig of capacity 250 PSIG & above 900 CMF & above in all strata including over budern upto 20 m. fixing of casing pipes, collars & cap with necessary cutting, threading & welding including transportation of rig and supporting vehicle, crew charges & cost of consumables etc., complete including yield testing at the final depth with minimum working of compressor for one hour(excluding cost of casing pipes, collars, cap etc.,) 50 to 100 m **Qty Upto 125%**	Rmtr	496.00	Rupees Four Hundred Ninety Six Only
4	2350.00	Sinking of borewell of 165 mm dia clear using super fast hydraulic rig of capacity 250 PSIG & above 900 CMF & above in all strata including over budern upto 20 m. fixing of casing pipes, collars & cap with necessary cutting, threading & welding including transportation of rig and supporting vehicle, crew charges & cost of consumables etc., complete including yield testing at the final depth with minimum working of compressor for one hour(excluding cost of casing pipes, collars, cap etc.,) 100 to 150 m **Qty Upto 125%**	Rmtr	511.00	Rupees Five Hundred Eleven Only

Executive Engineer
Project Division
Yelahanka Zone
BBMP, Bangalore-92

Scanned by TapScanner

	Quantity	Item Name	Unit	Approved Rates of M/s SATHYA BOREWELL CLEANING	
				In figures	In words
5	2350.00	Sinking of borewell of 165 mm dia clear using super fast hydraulic rig of capacity 250 PSIG & above 900 CMF & above in all strata including over budern upto 20 m. fixing of casing pipes, collars & cap with necessary cutting, threading & welding including transportation of rig and supporting vehicle, crew charges & cost of consumables etc., complete including yield testing at the final depth with minimum working of compressor for one hour(excluding cost of casing pipes, collars, cap etc.,) 150 to 200 m **Qty Upto 125%**	Rmtr	601.00	Rupees Six Hundred One Only
6	2350.00	Sinking of borewell of 165 mm dia clear using super fast hydraulic rig of capacity 250 PSIG & above 900 CMF & above in all strata including over budern upto 20 m. fixing of casing pipes, collars & cap with necessary cutting, threading & welding including transportation of rig and supporting vehicle, crew charges & cost of consumables etc., complete including yield testing at the final depth with minimum working of compressor for one hour(excluding cost of casing pipes, collars, cap etc.,) 200 to 250 m **Qty Upto 125%**	Rmtr	711.00	Rupees Seven Hundred Eleven Only
7	2350.00	Sinking of borewell of 165 mm dia clear using super fast hydraulic rig of capacity 250 PSIG & above 900 CMF & above in all strata including over budern upto 20 m. fixing of casing pipes, collars & cap with necessary cutting, threading & welding including transportation of rig and supporting vehicle, crew charges & cost of consumables etc., complete including yield testing at the final depth with minimum working of compressor for one hour(excluding cost of casing pipes, collars, cap etc.,) 250 to 300 m **Qty Upto 125%**	Rmtr	785.00	Rupees Seven Hundred Eighty Five Only
8	2300.00	Sinking of borewell of 165 mm dia clear using super fast hydraulic rig of capacity 250 PSIG & above 900 CMF & above in all strata including over budern upto 20 m. fixing of casing pipes, collars & cap with necessary cutting, threading & welding including transportation of rig and supporting vehicle, crew charges & cost of consumables etc., complete including yield testing at the final depth with minimum working of compressor for one hour(excluding cost of casing pipes, collars, cap etc.,) 300 to 350 m **Qty Upto 125%**	Rmtr	250.00	Rupees Two Hundred Fifty Only
9	1364.00	Sinking of borewell of 165 mm dia clear using super fast hydraulic rig of capacity 250 PSIG & above 900 CMF & above in all strata including over budern upto 20 m. fixing of casing pipes, collars & cap with necessary cutting, threading & welding including transportation of rig and supporting vehicle, crew charges & cost of consumables etc., complete including yield testing at the final depth with minimum working of compressor for one hour(excluding cost of casing pipes, collars, cap etc.,) 350 to above	Rmtr	1000.00	Rupees One Thousand Only
10	2083.50	Supplying of ISI Mark 175 mm nominal bore medium black ERW casing pipe of 5mm thick black electric resistance continous welded midle steel tube material confirming to IS 1387/1993 and manufactured from hot rolled steel skelp/stripes in random length of 4 to 7 mtr both ends threaded confirming to IS 554/1985 one end(including of all taxes)	Rmtr	1480.00	Rupees One Thousand Four Hundred Eighty Only

Executive Engineer
Project Division
Valparai Zone

Scanned by TapScanner

...AR PALIKE

	Quantity	Item Name	Unit	Approved Rates of M/s SATHYA BOREWELL CLEANING	
				In figures	In words
1	512.50	Providing and fixing 250mm dia PVC pipe and as per specification and directions. **Qty Upto 125%**	Rmtr	1250.00	Rupees One Thousand Two Hundred Fifty Only
	145.50	**Qty Above 125%**	Rmtr	1250.00	Rupees One Thousand Two Hundred Fifty Only
12	47.00	175 mm dia M.S. Casing cap	Each	103.00	Rupees One Hundred Three Only
13	362.00	M.S. Casing pipe collars 'C' Class	Each	154.00	Rupees One Hundred Fifty Four Only
14	1034000.00	Fabricating supplying and mounting MS box of 16 SWG suitable for floor / wall mounting, fully weather proof with provision for better hear description, (providing with hinged front cover, equipped with tamper proof locking arrangements, with suitable size clamps with necessary cable entry pipe with gland and box should be finished 2 coats of red oxide primes paint and finally finished with approved colour enamelled metal paint etc,. complete box of 21600 sq cm	Sqm	0.33	Rupees And Paise Thirty Three Only
15	2228.00	Labour charges for erection of new /repaired submersible pumpset along with GI pipes (32/50mm) cable (new submersible pumpset if required will be supplied by the department free of cost and released pump set should be handed over to department) including transportation (each length = 6.00m)	Each	92.00	Rupees Ninety Two Only
16	123.00	Supplying and fixing of Porcelain fuse channel with cut out on existing wooden / panel using necessary nuts, bolts and washer etc., complete....	No	234.00	Rupees Two Hundred Thirty Four Only
17	991.00	Supplying and laying of L.T.U.G Cable having aluminiumconductor PVC insulated shethed galvanised steel wire/ steel tape armoured cable with PVC outer sheathing 1.1 KV class 4 core 16 sqmm cable (confirming to IS 1554)	Mtr	140.00	Rupees One Hundred Forty Only
18	933.00	Digging of trenches of 0.6mm x 0.50 Mtrs wide refilling the trench to the required ground level and consolidating etc,. Complete sutting road surfaces	Mtr	117.00	Rupees One Hundred Seventeen Only
19	80.00	Supplying and fixing Class-A GI Pipe on pole/ wall/drain crossing with necessary clamping arrangements for UG Cable of 1.1 KV class 40mm	Mtr	294.00	Rupees Two Hundred Ninety Four Only
20	41.00	Supplying and fixing wiring earth electrode for grounding conduits, IC cutouts and other equipments on the meter board using 40mm dia 2.90 mm thick GI pipe 2.5 mtr long buried in a pit,/ the pit should be filled with equal proportion of salt and charocal 150 mm alround the pipe to complete depth the connections from the pipe to the conduit etc,. is to be established though GI wire of size as per ISI specification 7.3.3 of ISI 732 using 12mm dia boalts, nuts washers and checknuts etc,. the pipe shall have 16 through holes of 122mm dia	No	4317.00	Rupees Four Thousand Three Hundred Seventeen Only
21	41.00	Supply and fixing LT cast iron pot heads suitable for 1.1 KV class 16 sqmmUG cable filled with necessary bitumen/ insulating compound complete with terminals, clamps, bolts nuts and washers etc,	No	280.00	Rupees Two Hundred Eighty Only

Executive Engineer
Project Division
Yelahanka Zone
BBMP, Bangalore-92

Scanned by TapScanner

	ntity	Item Name	Unit	Approved Rates of M/s SATHYA BOREWELL CLEANING	
				In figures	In words
	41.00	Supplying and fixing of polished wood board made of not less than 15mm thick plank on both sides with planks made out on not more than 2 pieces and fixing the same to wall using tapered inverted wooden plugs screws etc., Size 20 x 20 x 2.5 inches	No	302.00	Rupees Three Hundred Two Only
	0.00	Cleaning of bore well inciuding yield tetsting of borewell either using slow or fast rig for not more than 2 hours at the final depth with air compressor or suitable pump as per specification (PRED 12-13 SL NO.9.5 PAGE NO.49)	Each	10128.00	Rupees Ten Thousand One Hundred Twenty Eight Only
	41.00	Borewell Clamp Set	Set	1800.00	Rupees One Thousand Eight Hundred Only
25	37.00	Supply & delivery at site brand new texmo/innoval/lubi/sabar /Atalanta/calamal/ waterman/Radha make suitable HP deep well submercible pumpset suitable for vertical installation in 150 dia borewells compressing of single stage or multistage CF pump close coupled by means of stainless steel coupling to suitable HP suitable speed totally enclosed and filled with pure drinking water squirrel cagesubmercible induction motor suitable for operation of 3Ph, 50Hz.380/440 volts AC supply fitted with required accessories such as suction, casing, suction strainers, sand guard. Non return valve etc Complete the pump and motor shall from an integral unit with all the required fittings 17.5HP 30 Stage **Qty Upto 125%**	No	72500.00	Rupees Seventy Two Thousand Five Hundred Only
	4.00	**Qty Above 125%**	No	72500.00	Rupees Seventy Two Thousand Five Hundred Only
26	0.00	Supply & delivery at site brand new texmo/innoval/lubi/sabar /Atalanta/calamal/ waterman/Radha make suitable HP deep well submercible pumpset suitable for vertical installation in 150 dia borewells compressing of single stage or multistage CF pump close coupled by means of stainless steel coupling to suitable HP suitable speed totally enclosed and filled with pure drinking water squirrel cagesubmercible induction motor suitable for operation of 3Ph, 50Hz.380/440 volts AC supply fitted with required accessories such as suction, casing, suction strainers, sand guard. Non return valve etc Complete the pump and motor shall from an integral unit with all the required fittings 20 HP 40 Stage	Rmtr	91800.00	Rupees Ninety One Thousand Eight Hundred Only
27	14284.00	Providing, laying & jointing GI pipes confirming to IS specification of approved make with fittings such as collars bends elbows tees nipples plugs with cuts threads using white lead & threads for joints wherever necessary as per direction including all lead & lift etc,. complete 'A' grade(excluding cost of fittings) 50mm dia GI pipe B Class	No	435.00	Rupees Four Hundred Thirty Five Only
28	2454.00	Supply and fixing Heavy Collar for GI Pipes 50MM	Mtr	0.88	Rupees And Paise Eighty Eight Only
29	30664.00	Supplying of submersible pump cable 1X3X6..0 Sq.mm	No	145.00	Rupees One Hundred Forty Five Only

Executive Engineer
Project Division
Yelahanka Zone
BBMP, Bangalore-92

Scanned by TapScanner

	uantity	Item Name	Unit	Approved Rates of M/s SATHYA BOREWELL CLEANING	
				In figures	In words
	41.00	Supplying & delivery at site brand new / Essen / Lotus sunsines/Adarsh/ Gk controls best indigenous make combine energy meter-cum-control panel board unit of size 1200 x 600 x 300 mm minimum mechanically strong and vermin and water proof the unit shall have two detachable doors suitable for operation on 3ph, 50Hz, 380/440 volts, AC supply with spring loaded latch locking with a key ribs should be provided inside the door , canopy apron and louvers ventilators shall be provided the combine energy mtr cum control panel board unit suitable for operation on 3ph, 50Hz, 380/440 AC supply shall be consisted etc,. completed T panel board shall be fabricated on single unit in the above components panel board for suitable pumpset above components panel board for suitable pumpset above Up to 20HP with star delta starter (MR)	No	21000.00	Rupees Twenty One Thousand Only
31	41.00	Supplying & delivery of brand 50mm Gate Valve.	No	1800.00	Rupees One Thousand Eight Hundred Only
32	41.00	Supplying & delivery of brand 50mm Non Return Valve.	No	1800.00	Rupees One Thousand Eight Hundred Only
33	41.00	Supplying and fixing MCB	No	900.00	Rupees Nine Hundred Only
34	8025.75	Earthwork excavation for foundation of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in Ordinary soil not exceeding 1.5 m in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m after breaking of clods complete as per specifications **Qty Upto 125%**	Cum	318.00	Rupees Three Hundred Eighteen Only
	596.25	**Qty Above 125%**	Cum	318.00	Rupees Three Hundred Eighteen Only
35	17835.00	Providing and installing at site of work 63mm (0.662) PVC Pipes of 6 kg / cm2 including cost of pipes and specials and labour, including lowering into trenches, laying true to line, level and perfect linking at joints leak proof including jointing of approved type with all labour and lift charges, handling charges including encasing the pipe alround to a depth not less than 15cms with gravel or selected earth available from the excavation etc., complete **Qty Upto 125%**	Mtr	395.00	Rupees Three Hundred Ninety Five Only
	1325.00	**Qty Above 125%**	Mtr	395.00	Rupees Three Hundred Ninety Five Only
36	8025.75	Refilling available earth around pipe lines, cables in layers not exceeding 20cms in depth, compacting each deposited layer by ramming after watering with lead upto 50m and lift upto 1.5m including cost of all labour complete as per specifications **Qty Upto 125%**	Cum	129.16	Rupees One Hundred Twenty Nine And Paise Sixteen Only
	596.25	**Qty Above 125%**	Cum	129.16	Rupees One Hundred Twenty Nine And Paise Sixteen Only

Executive Engineer
Project Division
Yelahanka Zone
BBMP, Bangalore-92

Scanned by TapScanner

	uantity	Item Name	Unit	Approved Rates of M/s SATHYA BOREWELL CLEANING	
				In figures	In words
	1.00	Supply & delivery at site brand new texmo/innoval/lubi/sabar /Atalanta/calamal/ waterman/Radha make suitable HP deep well submercible pumpset suitable for vertical installation in 150 dia borewells compressing of single stage or multistage CF pump close coupled by means of stainless steel coupling to suitable HP suitable speed totally enclosed and filled with pure drinking water squirrel cagesubmercible induction motor suitable for operation of 3Ph, 50Hz.380/440 volts AC supply fitted with required accessories such as suction, casing, suction strainers, sand guard. Non return valve etc Complete the pump and motor shall from an integral unit with all the required fittings For 15HP 35 Stage	Each	67724.00	Rupees Sixty Seven Thousand Seven Hundred Twenty Four Only
E-2	1.00	Supply & delivery at site brand new texmo/innoval/lubi/sabar /Atalanta/calamal/ waterman/Radha make suitable HP deep well submercible pumpset suitable for vertical installation in 150 dia borewells compressing of single stage or multistage CF pump close coupled by means of stainless steel coupling to suitable HP suitable speed totally enclosed and filled with pure drinking water squirrel cagesubmercible induction motor suitable for operation of 3Ph, 50Hz.380/440 volts AC supply fitted with required accessories such as suction, casing, suction strainers, sand guard. Non return valve etc Complete the pump and motor shall from an integral unit with all the required fittings For 7.5HP 75 Stage	Each	46909.00	Rupees Forty Eight Thousand Nine Hundred Nine Only
E-3	340.00	KSRB13-9.2 : Providing and fixing to wall, ceiling and floor high density polyethylene pipes 6.00 kgf/sq.cm working pressure of outside diameter raising mains & exposed distribution pipes with special flange, compression type fittings, wall clips, making good the wall, ceiling and floor, including cost of all materials, labour charges, HOM of equipments and testing complete as per specifications. - do- 40mm dia	Mtr	262.00	Rupees Two Hundred Sixty Two Only

Executive Engineer
Project Division
Yelahanka Zone
BBMP, Bangalore-92

Scanned by TapScanner